



Acel part number AC0599

Solar Commissioning Multifunction Tester

Insulation Test

Tests a Single Module, String or an Entire Photovoltaic Field up to 1000V

Open Circuit Voltage Measurement

Short Circuit Current Measurement

Continuity Measurement

Polarity

Auto Sequence

Technical Specification

| Attribute | Value |
|-------------------------|-------------------------|
| Insulation Measurement | Up to 1000V DC |
| Open Circuit Voltage | Up to 1000V DC |
| Short Circuit Current | Up to 15Amp at 1000V DC |
| Continuity | 200mA |
| Polarity | Yes |
| Auto Sequence | Yes |
| Performance Logging | Yes |
| Optional Reference Unit | Yes (HT304N) |
| Hard Carry Case | Yes |
| | |
| | |
| | |
| | |

9-AC0599-2023-V1